JHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

NAME OF WORK: Pot holes Filling in ward no.12, in Shettyhalli Sub-Division

Sl.No	Description of work	Unit	Qty	Sanctioned Estimate Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods Complete as per specifications.	Cum	158.00	58.32	Rupees Fifty Eight and Thirty Two Paise Only
2	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam Specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density Complete as per specifications.	Cum	157.55	1059.48	Rupees One Thousand Fifty Nine and Forty Eight Paise Only
3	Tack coat:- Providing and laying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/Granular surface cleaned with mechanical broom. Complete as per specifications.	Sqm	787.74	12.74	Rupees Twelve and Seventy Four Paise Only
	Filling Pot-Holes and patch repairs with Bituminous Concrete, 40mm. KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2Complete as per specifications.	Sqm	787.74	378.00	Rupees Three Hundred Seventy Eight Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer

4	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading Complete as per specifications.	Cum	158.00	100.35	Rupees One Hundred and Thirty Five Paise Only

Signature of Contractor

EXECUTIVE ENGINEER-4
KRIDL, BDMP DIVISION
BENGALURU-560 010

Executive Engineer,
Dasarahalli Division,